



Wicomico County Purchasing
 125 N. Division St. Room B-3
 Salisbury, MD 21801
 Ph. 410-548-4805 Fax 410-334-3130
 Email: purchasing@wicomicocounty.org

Addendum # 1 Underground Fuel Tank Removal at Detention Center

Date of Addendum: 10/28/2020

NOTICE TO ALL BIDDERS AND PLANHOLDERS

The Bid Documents for the above-referenced Project are modified as set forth in this Addendum. The original Bid Documents and any previously issued addenda remain in full force and effect, except as modified by this Addendum, which is hereby made part of the Bid Documents. Vendors will take this Addendum into consideration when preparing and submitting a bid, and shall acknowledge receipt of this Addendum in the space provided in the Bid Documents.

BID SUBMITTAL DEADLINE

The bid submittal time has been changed from Wednesday, November 4, 2020 at 2:30p.m. to Wednesday, December 2, 2020 at 2:30p.m.

1.0 – QUESTIONS AND ANSWERS

The following questions and answers are provided as a matter of information to clarify issues raised about the Bid Documents.

Item	Questions and Answers
1.1	Q. Tank seems too close to the emergency generator. Is filling in place an option? According to MDE it is with a letter from an engineer stating that it would be a hazard to remove. A. To be determined. Awaiting reply from MDE. Not available until 11/2.
1.2	Q. If tank is removed and gravel is encountered, can it be left in place and covered with filter fabric to eliminate settling? A. Yes
1.3	Q. If concrete hold down pad is encountered, can it be left in place? A. Yes
1.4	Q. Is county responsible for locating all utilities and if in the way, responsible for relocating? A. Yes. This was completed 10/26.
1.5	Q. Please provide as-built drawings that include the depth of the concrete slab that is near the underground storage tank. A. The generator is mounted on a reinforced concrete slab on grade approximately 10” thick. There is no sub-base or other reinforcing/supporting means. There are no drawings available. This information was obtained from the installation contractor.
1.6	Q. Please confirm any known utilities in the area of excavation. A. Site was surveyed and utilities marked on 10/26. There are no major obstructions, only those associated with the tank.
1.7	Q. Please confirm if compaction testing is required. A. Compaction testing is not required. However, fill shall be placed in 6 – 8” lifts and vibratory tamped at each lift.
1.8	Q. Would it be possible to schedule a site visit as we were unable to attend the Pre-bid meeting last week? A. Yes, dependent upon staff availability.

END OF ADDENDUM