



Wicomico County Purchasing
125 N. Division St. Room B-3
Salisbury, MD 21801
Ph. 410-548-4805 Fax 410-334-3130
Email: purchasing@wicomicocounty.org

Addendum # 2 Replacement of Basketball Court Fencing at Willards Park

Date of Addendum: 04/23/19

NOTICE TO ALL BIDDERS AND PLANHOLDERS

The Bid Documents for the above-referenced Project are modified as set forth in this Addendum. The original Bid Documents and any previously issued addenda remain in full force and effect, except as modified by this Addendum, which is hereby made part of the Bid Documents. Vendors will take this Addendum into consideration when preparing and submitting a bid, and shall acknowledge receipt of this Addendum in the space provided in the Bid Documents.

BID SUBMITTAL DEADLINE

The bid submittal time has not been changed.

1.0 – QUESTIONS AND ANSWERS

The following questions and answers are provided as a matter of information to clarify issues raised about the Bid Documents.

Item	Questions and Answers
1.1	Q. Please confirm the total footage of this project. I rolled off two lines of 51' long. [If the two fence lines are made to be 50' long each, then this works better (50') for even 10' post centers.] A. Each side should be 50' in length
1.2	Q. Please confirm that all posts and concrete footers are to be pulled/disposed of and their holes back-filled? A. All the footers and post are to be removed and backfilled
1.3	Q. You are asking us to bid 1 3/4" x 11 ga. galvanized chain link fabric. Would you consider using 2" mesh x 9 ga. galvanized chain link instead? (9 ga. is stronger fabric). A. Change the fabric to 2" mesh x 9 gauge.
1.4	Q. Please confirm that item 2.c. is an error. You want all terminal posts to be 3" O.D. – brace & trussed. A. All terminal post should be 3" O.D. with brace and trusses.

END OF ADDENDUM